

9-4  
23  
R  
4-071004

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-195-21,160-00-00

SE SE SE /4 SEC. 10, 13 S, 21 W  
330 feet from S section line  
330 feet from E section line

Operator license# 7973

Lease Deutscher well # 1

Operator: AL-LA-LYN Oil, Inc.

County Trego

Address: 614 W. 10th Street  
Ellis, Kansas 67637  
Robert A. Wahlmeier

Well total depth 3911 feet <sup>127.10</sup>  
Conductor Pipe: 0 inch @ 331 feet  
Surface pipe 8 5/8 Inch @        feet

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Allied Cementing Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 4 Month: September Year: 92

Plugging proposal received from: Robert A. Wahlmeier

Company: AL-LA-LYN Oil Company Phone: 913-726-3545

Were: 8 5/8" - 331' S.P. cwc. w/180 sx. 5 1/2" casing set @ 3905'  
w/100 sx. cement. D.V. @ 1573' cwc. w/450 sx. cement. Perfs. 3813' -  
3474'. Anhy. 1553'. Proposal - Run wireline to T.D. - Order 350 sx.  
65/35 pozmix - 8% gel. and 5 sx. hulls. Pump in with pump truck. Load  
both 5 1/2" casing and 5 1/2" x 8 5/8" annulus with cement top to bottom.  
Shut in under pressure.

Plugging Proposal Received by: Marion J. Schmidt  
Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 11:20A.M., Day: 4, Month: September, Year: 92

Actual plugging report: AL-LA-LYN ordered 350 sx. 65/35 pozmix - 8% gel. -  
5 sx. hulls. Pumped cement in with pump truck.

- 1) Ran wireline to T. D. 3821'.
- 2) Pressured 5 1/2" x 8 5/8" annulus with cement w/15 sx. cement. Max.  
pressure 350 P.S.I. Shut in @ 350 P.S.I.
- 3) Pumped 15 sx. cement in 5 1/2" casing followed with 320 sx. 65/35  
posmix - 8% gel. with 5 sx. hulls added in. Max. pressure 100 P.S.I.  
Shut in @ 50 P.S.I.

Remarks: Cemented by Allied Cement.  
Condition of casing(in hole): GOOD X BAD     Anhy. plug: YES X NO      
Bottom plug(in place): YES X, CALC    , NO     Dakota plug: YES X, NO      
Plugged through TUBING    , CASING X. Elevation: 2185 GL

I did[ X ] / did not[     ] observe the plugging.

DATE 9-30-92  
INV. NO. 36280

Marion J. Schmidt  
(agent)

RECEIVED  
SEP 18 1992  
CONSERVATION DIVISION  
WICHITA, KANSAS