

6 030921

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-112-195-21,175-00-00

SW SW NW, SEC. 10, T 13 S, R 21 W/E
2970 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4678

Lease Name Cox Well # 3

Operator: Lasmo Energy Corp.
Name & Address: P.O. Box 1365
Great Bend, Kansas 67530

County Trego 127.01

Well Total Depth 3908 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 291'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B.J. Titan License Number _____

Address Hays, Kansas

Company to plug at: Hour: AM Day: 31 Month: 7 Year: 19 87

Plugging proposal received from Buster Humphrey

(company name) Lasmo (phone) _____

were: 8 5/8" set at 291' with 165 sx 5 1/2" set at 3898 w/ 150 sx PBDT

3890' Portcollar @ 1474' cmt. Basket @ 1553 T.O.C. near 1000' Plug over art buckle at

3890' Perf top 3472. Order sandsand com. cmt. shoot and pull pipe order 125 sx. thrifty mix

65/35 poz. 10% gel 2% dicel 5 sx hulls B.J. Titan Cmt Co. Sundowner Water Truck

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9: AM Day: 31 Month: 7 Year: 19 87

ACTUAL PLUGGING REPORT Sand bottom to 3400 w/5 sx. com. cmt. on sand with

bailer. 2 shots recovered 900' of 5 1/2" csg.

Squeezed 8 5/8" csg w/5 sx hulls mixed in w/ 125' sx cmt. blend.

Max. P.S.I. 700 # Close in PSI 300 # plug complete.

RECEIVED
STATE CORPORATION COMMISSION
AUG 18 1987
08-18-1987
CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____

(if additional description is necessary, use BACK of this form.)

I (did not observe) this plugging.

Signed Carl Goodrow (TECHNICIAN)

DATE 8-18-87

aj INV. NO. 17862

Carl Goodrow