

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

15-195-20157-00-00

Trego County, Sec. 7 Twp. 13 Rge. 21 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines SW NE NE
Lease Owner Leo J. Dreiling Oil Co.
Lease Name Glass Well No. #2
Office Address R. R. #2 ; Victoria, Kansas 67671
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____
Application for plugging filed August 1970
Application for plugging approved August 1970
Plugging commenced August 26 1970
Plugging completed September 1 1970
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production August 15, 1970
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	187	None
				4 1/2"	3932	3190

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

August 26, 1970 Plugged off bottom. Dumped sand to 3755'. Mixed and dumped 4 sx of cement to 3705'.

September 1, 1970 Plugged off top. Sun Oil Well Cementing Co. mixed and pumped down 8 5/8" surface casing:
5 sx of halls
10 sx gel
100 sx of cement
7 sx gel
Released plug and mixed and pumped:
25 sx of cement
3 sx gel
10 sx of cement

RECEIVED
STATE CORPORATION COMMISSION
SEP 11 1970
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor RUSS CASING PULLING, INC.
Address P. O. BOX 1082 ; GREAT BEND, KANSAS 67530

STATE OF KANSAS, COUNTY OF ELLIS, ss.
LEO F. DREILING (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling
LEO F. DREILING - RR#2 VICTORIA, KANSAS 67671
(Address)

Subscribed and Sworn to before me this 3 day of SEPTEMBER, 1970



My commission expires SEPTEMBER 19, 1970

Joseph A. Hess
Notary Public.

L. J. DREILING AND SONS, INC.

Victoria, Kansas 67671

15-195-20157-00-00

WELL LOG

Company **Leo J. Dreiling Oil Co.**
Route #2
Victoria, Kansas 67671

Sec. 7 Twp. 13 Rng. 21

Farm **Class** No. 2

Location **SW NE NE**

Total Depth **4000'**

County **Trego**

Comm. **5-6-70** Comp. **5-13-70**

Elevation: **2262'** K. B.

2259' D. F.

2257' G. R.

Contractor **L. J. Dreiling & Sons, Inc.**
Victoria, Kansas 67671

Casing Record

Cement Record

Production:

187' - 8 5/8"
3932' - 4 1/2"

150 sacks cement
150 sacks common salt saturated cement

Figures Indicate Bottom of Formations

0'	90'	Surface soil & sand
90'	203'	Shale
203'	572'	Shale
572'	1180'	Shale
1180'	1390'	Dakota Sand
1390'	1683'	Shale & Red Bed
1683'	1723'	Anhydrite
1723'	2015'	Shale & Red Bed
2015'	2230'	Shale & Salt
2230'	2380'	Shale & Lime
2380'	2643'	Shale & Lime
2643'	2743'	Lime & Shale
2743'	2935'	Lime & Shale
2935'	3096'	Lime & Shale
3096'	3245'	Lime
3245'	3397'	Lime
3397'	3546'	Lime & Shale
3546'	3642'	Lime
3642'	3650'	Lime
3650'	3677'	Lime
3677'	3777'	Lime
3777'	3780'	Lime
3780'	3840'	Lime
3840'	3942'	Lime
3942'	4000'	Lime
4000'	T.D.	

RECEIVED
STATE CORPORATION COMMISSION

AUG 24 1970

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Class #2.

Leo F. Dreiling
LEO F. DREILING

Subscribed and sworn to before me this 19th day of May, 1970.

Joseph A. Hess
JOSEPH A. HESS - NOTARY PUBLIC

Commission expires: September 19, 1970

