

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Trego County. Sec. 7 Twp. 13S Rge. 21W /E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
C N/2 NE/4 SW/4


Lease Owner Gear Petroleum Co., Inc.
Lease Name Herl Well No. 3
Office Address 300 Sutton Place, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) D & A

Date Well completed May 6, 1980
Application for plugging filed May 6, 1980
Application for plugging approved May 6, 1980
Plugging commenced May 7, 1980
Plugging completed May 7, 1980
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gil Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 14,040'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	246'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug #1 @ 640' w/70 sx cement
#2 @ 240' w/20 sx cement
Bridge @ 40' w/10 sx cement
5 sx cement in rathole
50-50 Pozmix, 6%

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company
1720 KSB&T Building, Wichita, Kansas 67202


STATE OF Kansas COUNTY OF Sedgwick, ss. contractor
Gloria Fawcett (employee of ~~owner~~ or ~~lessee~~ or ~~operator~~)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gloria Fawcett
1720 KSB&T Building, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of May, 1980.

My commission expires _____

Joyce A. Hagermann
Notary Public.
MAY 15 1980
CONSERVATION DIVISION
Wichita, Kansas



MAY 14 1980

15-195-20641-00-00

DRILLERS LOG

No. 3 Herl

CASING RECORD:	COMPANY:	Gear Petroleum Co., Inc.	DESCRIPTION:
8 5/8" @ 254'	CONTRACTOR:	Red Tiger Drilling Company	C N/2 NE/4 SW/4
w/195 sx cement	COMMENCED:	April 24, 1980	Sec. 7-T13S-R21W
D & A	COMPLETED:	May 7, 1980	Trego County, Kansas
TOTAL DEPTH: 4,040'			ELEVATION: 2,219' KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale, Sand & Shale	0	265	
Shale	265	940	
Shale & Red Bed	940	1140	
Sand	1140	1340	
Shale	1340	1654	
Anhydrite	1654	1706	
Shale	1706	2670	
Shale & Lime Streaks	2670	2870	
Shale & Lime	2870	3393	
Lime	3393	4040	
RTD		4040	

I certify that this is a true and correct copy of the above log to the best of my knowledge..

RED TIGER DRILLING COMPANY

Gloria Fawcett

 Gloria Fawcett

Subscribed and sworn to before me this 13th day of May, 1980.

Joyce A. Hagermann

 Notary Public

