

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-195-21,717-00-00

LEASE NAME Denning

WELL NUMBER 4

SPOT LOCATION W/2 NW/4 NW/4

SEC. 20 TWP. 13S RGE. 21W (E) or (W)

COUNTY Trego

Date Well Completed 5/4/85

Plugging Commenced 5/4/85

Plugging Completed 5/4/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Strata Energy Resources Corporation
2905 Redhill Avenue, Suite 201
ADDRESS Costa Mesa, California 92626

PHONE # (714) 261-8181 OPERATORS LICENSE NO. 5302

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dave Wans, Hays, Kansas 67601

Is ACO-1 filed? YES If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 4,010'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	252.39'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

1st Plug @ 4000' w/20 sx cement; 2nd Plug @ 1660' w/20 sx cement;
3rd Plug @ 835' w/100 sx cement and 1 sx Floseal;
4th Plug @ 300' w/40 sx cement; Bridge Plug from 40' to 0' w/10 sx cement;
10 sx cement in rathole (Plugs calculated by displacement)
200 sx 50/50 Pozmix, 6% Gel, 3% CC

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company License No. N/A

Address Box 31, 332 W. Wichita, Russell, Kansas 67665

RECEIVED
STATE CORPORATION COMMISSION


STATE OF _____ COUNTY OF _____, ss.

(employee of operator) or CONSERVATION DIVISION
(operator) of above-described well, being first duly sworn on oath, says: Wichita, Kansas
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) [Signature]

(Address) 4101 Birch St. Newport Beach, ca

SUBSCRIBED AND SWORN TO before me this 11th day of June, 1985



[Signature]
Notary Public

My Commission expires: May 22, 1987