


15-195-00092-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Trego County. Sec. 22 Twp. 13 Rge. (E) 21 (W)
Location as "NE/CNW/SW" or footage from lines NW/4 NW/4 NE/4
Lease Owner Renfro Drilling Co.
Lease Name Sauer Well No. 1
Office Address 316 Insurance Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 28 1959
Application for plugging filed July 28 1959
Application for plugging approved July 28 1959
Plugging commenced July 28 1959
Plugging completed July 28 1959
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius, Hill City, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3970 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	231'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.


Filled with heavy mud from 3970' up to 550'.
Set Plug #1 at 550'. Mixed 20 sax cement.
Filled with mud from 490' up to 250'. Set
Plug #2 at 250'. Mixed 20 sax cement.
Filled with mud from 190' up to 40'. Set
Plug #3 at 40'. Mixed 10 sax cement.

RECEIVED
STATE CORPORATION COMMISSION
AUG 4 1959 08-04-59
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Renfro Drilling Co.
Address 316 Insurance Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Henry D. Ficken (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Henry D. Ficken
316 Insurance Bldg., Wichita, Kansas
(Address)



Subscribed and sworn to before me this 30th day of July, 1959
Rorraine Hullbutt
Notary Public.

PLUGGING
FILE SEC. 32113 R-314
BOOK PAGE 52 LINE 41

Renfro Drilling Co., Sauer #1
NW NW NE Sec. 22-13S-21W
Trego County, Kansas

Commenced - July 13, 1959
Completed - July 28, 1959
Casing - 231' of 8-5/8" w/150 sax HA5
Elevation - 2258 KB

RECEIVED
STATE CORPORATION COMMISSION
AUG 4 1959
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

0 - 231	Surface
231 - 395	Shale
395 - 940	Shale
940 - 1415	Shale
1415 - 1620	Shale
1620 - 1666	Anhydrite
1666 - 1825	Shale
1825 - 1975	Shale and lime
1975 - 2200	Shale
2200 - 2320	Shale and lime
2320 - 2520	Lime and shale
2520 - 2605	Lime
2605 - 2820	Lime and shale
2820 - 2960	Lime
2960 - 3135	Lime and shale
3135 - 3243	Lime
3243 - 3327	Lime and shale
3327 - 3440	Lime
3440 - 3550	Lime
3550 - 3561	Lime
3561 - 3582	Lansing
3582 - 3696	Lime
3696 - 3775	Lime
3775 - 3802	Lime
3802 - 3845	Lime and shale
3845 - 3913	Lime and chert
3913 - 3930	Shale
3930 - 3940	Lime
3940 - 3942	Arbuckle
3942 - 3950	Arbuckle
3950 - 3955	Lime
3955 - 3970	Lime
3970 -	Rotary Total Depth D&A

STATE OF KANSAS)
) SS
SEDGWICK COUNTY)

I, the undersigned, being duly sworn on oath, state that the above Drillers Log is true and correct to the best of my knowledge and belief and according to the records of this office.

RENFRO DRILLING CO.

By Henry D. Fickson

Subscribed and sworn to before me this 31st day of July, 1959.

Lorraine Shillcutt
Notary Public

My commission expires June 1, 1960.



PLUGGING
FILE SEC. 22 T 13 R 21 W
BOOK PAGE 57 LINE 41