

15-195-20159-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 9 1970
CONSERVATION DIVISION
Wichita, Kansas

06-09-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Walters Drilling Company,

Complete Address 400 Insurance Building, Wichita, Kansas.

Lease Name Birch Well No. 1

Location CSE-NW Sec. 2 Twp. 13 Rge. (E) (W) 22

County Trego Total Depth 4175'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Rains & Williamson Oil Company, Incorporated,

Address 1125 Wichita Plaza Building, Wichita, Kans. License No.

Operation Completed: Hour 5:00 PM Day 6 Month 6 Year 1970

The above well was plugged as follows:

248'---8 5/8" Surface casing, cement circulated with 175 Sx.

Top of Dakota section @ 672'.

Circulated hole with heavy mud. Pulled DP to 900' and displaced 100 Sx. cement thru

DP from 900' to 575'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from

275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to

bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. B. Nichols
Well Plugging Supervisor

DATE 6/9/70

INV. NO. 2023-W