

15-195-00023-00-00

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NW NW NE

SEC. 31 TWP. 13 RGE. 21

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Bongraf F Tz

Operator Jones Shelburn Farmer Address Russell, Kans

Field _____ County Trego

Total Depth 4230 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 200 circulated with cement - 5 1/2" at 4230' with
100 sax cement behind - Lane Wells plugs to 4142'-top
perforations at 4122'.

Filled with chat to 4115', set 4 sax cement with dump
bailer, pulled 3487' 5 1/2", filled hole with mud to 200',
set rock and 15 sax cement, mud to 35', set rock and 10
sax to bottom cellar.

RECEIVED

STATE CORPORATION COMMISSION

PLUGGING

FILE SEC. 31 T. 13 R. 21 14 1952
BOOK PAGE 29 LINE 1 CONSERVATION DIVISION
Wichita, Kansas

[Signature]
District Conservation Agent

Date 7-10-52