

15-195-20247-00-00

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 4 1974  
06-04-74  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Rains & Williamson Oil Company, Incorporated,

Complete Address 435 Page Court, 220 West Douglas, Wichita, Kansas.

Lease Name Flax Well No. 1

Location NW-SE-NE Sec. 30 Twp. 13 Rge. (E) (W) 21

County Trego Total Depth 4150'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Gasing Pulling Company, Incorporated,

Address Box #405, Chase, Kansas. License No. 624

Operation Completed: Hour 10:00 AM Day 31 Month 5 Year 1974

The above well was plugged as follows:

246'--8 5/8" Surface casing, cement circulated with 160 Sx.

4149'--5 1/2" Casing cemented on bottom with 125 Sx.

Sanded well back to 4120' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing  
(3366)' and squeezed well initially with 5 sacks hulls and 17 sacks gel and followed  
with 110 Cu. Ft. cement from 750' to 425' then 4 sacks gel from 425' to 265' and  
followed with 30 Cu. Ft. cement from 265' to 190'. then 4 sacks gel from 190' to 30'  
and finally 10 Cu. Ft. cement from 30' to bottom of cellar. (Mudding and cementing  
operations performed by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: W. S. Nichols  
Well Plugging Supervisor

INVOICED

DATE 6/5/74  
INV. NO. 9234-W