

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

15-195-19051-00-00

FILE NO. _____

LOCATION SW SE SW

SEC. 32TWP. 13RGE. 21W

Dry Hole Abandoned Oil Well Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 1 Lease Pinney Box 690 Chickasha, Okla.
Operator Superior Oil Company Address Wichita, Kans
Field _____ County Trego

Total Depth 4109 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address _____

(Describe briefly the manner in which the well was plugged)

10 3/4" at 247' circulated with cement - 7" at 4109' with
150 sax cement behind - Lane Wells plugs at 4070', perforated
at 4050'
Filled with sand to 4040' set 5 sax cement with dump bailer,
pulled 3285' 7", filled with mud to 248', set rock and 20 sax
cement, mud to 35', set rock and 10 sax cement to bottom cellar.

PLUGGING
FILE SEC 32 T 13 R 21 W
BOOK PAGE 24 LINE 27

RECEIVED
STATE CORPORATION COMMISSION
APR 2 1954
04-02-54
CONSERVATION DIVISION
Wichita, Kansas

J. Edgar Petty
District Conservation Agent
Date 3-31-54