

15-195-20301-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

SEP 30 1974

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Donald C. Slawson,

Complete Address 408 One-Twenty Building, Wichita, Kansas.

Lease Name Schmeidler 'B' Well No. B-1

Location SW-NE-SE Sec. 11 Twp. 13 Rge. (E) (W)22

County Trego Total Depth 3830'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Slawson Drilling Company, Incorporated,

Address Above License No.

Operation Completed: Hour 4:45 PM Day 27 Month 9 Year 1974

The above well was plugged as follows:

271'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 675'.

Circulated hole with heavy mud. Pulled DP to 900' and displaced 110 Cu. Ft. cement
thru DP from 900' to 575'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru
DP from 310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *K. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 10/11/74
INV. NO. 3-W