

15-195-20096-00-00

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED

STATE CORPORATION COMMISSION

DEC 17 1968

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Walters Drilling Company & Mull Drilling Company,

Complete Address: 400 Insurance Building, Wichita, Kansas.

Lease Name Schmeidler Well No. 1

Location CSE-SE Sec. 11 Twp. 13 Rge. (E) (W) 22

County Trego Total Depth 4125'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Walters Drilling Company,

Address: 400 Insurance Building, Wichita, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 12:15PM Day 12 Month 12 Year 1968

The Above well was plugged as follows:

211'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 585'.

Circulated hole with heavy mud. Pulled DP to 800' and displaced 100 Sx. cement thru  
DP from 800' to 475'. Pulled DP to 240' and displaced 25 Sx. cement thru DP from 240'  
to 165'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/17/68  
INV. NO. 9033-U

Signed: M. L. DeChale  
Well Plugging Supervisor