

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

AUG 28 1974

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Mack Oil Company

Complete Address 812 Union Center Wichita, Kansas

Lease Name Alvin Well No. 1

Location NW NE NE Sec. 12 Twp. 13 Rge. (E) (W) 22

County Trego Total Depth 4080'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated     

Plugging Contractor Rains & Williamson Drlg.

Address Wichita, Kansas License No.     

Operation Completed: Hour 11 P Day 25 Month 8 Year 1974

The above well was plugged as follows:

RTD 4080' 8 5/8 csg set at 253' cwc Cem. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 750' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 240' & displaced 20 sk cmt thru drill pipe. Heavy  
mud to 40' built solid bridge & 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/29/74

INV. NO. 9792-W

Signed: R. J. Massey  
Well Plugging Supervisor