


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15 051 04613 00 00  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

ELLIS CO., KANSAS County. Sec. 27 Twp. 13S Rge. 17W (E) (W)

Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines NE SE SE  
Lease Owner OIL PROPERTIES MANAGEMENT, INC.  
Lease Name DREILING 'B' Well No. 4  
Office Address 603 Orpheum Building  
Character of Well (completed as Oil, Gas or Dry Hole) D & A  
Date well completed 3-11-59 19  
Application for plugging filed 3-11-59 19  
Application for plugging approved 3-11-59 19  
Plugging commenced 3-11-59 19  
Plugging completed 3-11-59 19  
Reason for abandonment of well or producing formation \_\_\_\_\_



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3585' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	197'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Fill with heavy mud to 550' set plug  
with 20 sx cement. Fill with heavy  
mud to 180' set plug with 20 sx cement.  
Fill with heavy mud to 40' set solid  
bridge with 10 sx cement to base of  
cellar. Job complete 3-11-59.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 25 1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor K & E DRILLING, INC.  
Address 719 Union Center, Wichita 2, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Dale Silcott (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me, God.

(Signature) Dale Silcott  
Dale Silcott, of K & E DRILLING, INC.  
719 Union Center, Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 11th day of March, 19 59

My commission expires August 11th, 1962.

Patricia M. Edwards  
Patricia M. Edwards, Notary Public.



PLUGGING  
FILE SEC. 27 T. 13 R. 17W  
BOOK PAGE 23 LINE 32

DRILLER'S

LOG

15-051-04613-00-00

OPERATOR: OIL PROPERTIES MANAGEMENT, INC. WELL: #4 DREILING 'B'  
 603 Orpheum Building  
 Wichita 2, Kansas LOCATION: NE SE SE  
 Sec. 27-13S-17W  
 CONTR: K & E DRILLING, INC. ELLIS COUNTY, KANSAS  
 719 Union Center  
 Wichita 2, Kansas COMMENCED: March 4th, 1959  
 COMPLETED: March 11th, 1959  
 CASING: 8-5/8' @ 197' (160 sx)  
 R.T.D. 3585' ELEVATION: unknown  
 PRODUCTION: D & A

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Shale	197
Shale & Red Bed	550
Sand & Shale	1180
Anhydrite	1210
Shale	1810
Shale & Shells	2030
Lime & Shale	2755
Shale & Lime	3035
Lime & Shale	3135
Lime	3220
Shale & Lime	3295
Lime	3470
Shale & Lime	3519
Lime	3550
Conglomerate Lime	3585
R.T.D.	3585

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 MAR 25 1959  
 CONSERVATION DIVISION  
 Wichita, Kansas

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 MAR 25 1959  
 CONSERVATION DIVISION  
 Wichita, Kansas

**CERTIFICATION**

STATE OF KANSAS )  
 ) SS:  
 COUNTY OF SEDGWICK )

I, Dale Silcott of K & E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

*Dale Silcott*  
 \_\_\_\_\_  
 Dale Silcott

Subscribed and sworn to before me this 18th day of March, 1959.

*Patricia M. Edwards*  
 \_\_\_\_\_  
 Patricia M. Edwards, Notary Public

My commission expires: August 11th, 1962.



**PLUGGING**  
 FILE SEC. 27 T. 13 R. 17W  
 BOOK PAGE 23 LINE 32