

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33554
Name: K. & B. Norton Oil & Investments, L.L.C.
Address 1: 1209 W. Park Grove Dr.
Address 2: _____
City: Manhattan State: KS Zip: 66503 + 2469
Contact Person: Ken Norton
Phone: (785) 320-2545
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 203-20156-00-00
Spot Description: _____
SE SW NW SE Sec. 21 Twp. 16 S. R. 35 East West
1,570 Feet from North / South Line of Section
2,220 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Wichita
Lease Name: Harp Well #: 1
Date Well Completed: _____
The plugging proposal was approved on: 11/15/10 (Date)
by: Mike Maier (KCC District Agent's Name)
Plugging Commenced: 11/14/10
Plugging Completed: 11/14/10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	287.7'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st Plug @ 2550' w/50 sks.; 2nd Plug @ 1550' w/80 sks.; 3rd Plug @ 750' w/40 sks.;
4th Plug @ 300' w/50 sks.; 5th Plug @ 60' w/30 sks.; 6th Plug @ Mousehole w/20 sks. &
7th Plug @ Rathole w/30 sks.
Total 300 sks. 60/40 Pozmix, 4% Gel, 1/4# Floseal

Plugging Contractor License #: 33793 Name: H2 Drilling, L.L.C.
Address 1: 10500 E. Berkeley Square Parkway Address 2: Suite 100
City: Wichita State: KS Zip: 67206 + 6816
Phone: (316) 636-2090

Name of Party Responsible for Plugging Fees: K. & B. Norton Oil & Investments, L.L.C.
State of Kansas County, Riley, ss.
Kenneth A. Norton Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Kenneth A. Norton

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
FEB 14 2011
KCC WICHITA *DL*