

API NUMBER 15-051-22,773-00-00
 LEASE NAME DISNEY B
 WELL NUMBER #3-18
1680 Ft. from N Section Line
1030 Ft. from E Section Line
 SEC. 18 TWP. 13S RGE. 19W (E) or (W)

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Graham-Michaelis Corp.
 ADDRESS P.O. Box 247, Wichita, KS 67201
 PHONE (316) 264-8394 OPERATORS LICENSE NO. 5134

COUNTY Ellis
 Date Well Completed _____
 Plugging Commenced 12-26-95
 Plugging Completed 12-28-95

Character of Well Oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)
 The plugging proposal was approved on _____ ? (date)
 by _____ ? (KCC District Agent's Name).
 Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3785
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 367' | none |
| | | | | 4-1/2" | 3784' | none |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set
RU Maier Well Service, laved out tubing & rods - 12-26-95. Allied Cementing RU to plug well. Pumped on the backside, pressured up to 300# PSI with no cement. Tied on to the 4-1/2" casing and mixed 25 sacks of 60/40 poz mix with 10% gel, 200# of hulls, 10 sacks of gel spacer & 150 sacks of 60/40 poz mix with 10% gel and 200# hulls. Casing pressured up to 1,000# PSI. Shut the well in. Well plugged 12-28-95.

Name of Plugging Contractor MAIER WELL SERVICE, INC. License No. _____
 Address _____

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Graham-Michaelis Corporation

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Jack L. Yinger - Vice President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Jack L. Yinger
 Jack L. Yinger - Vice President
 (Address) P.O. Box 247, Wichita, KS 67201

SUBSCRIBED AND SWORN TO before me this 10th day of January, 19 96

GLEND A. NEWELL
 Notary Public - State of Kansas
 My Appt. Expires 7/2/97

Glenda G. Newell
 Glenda G. Newell, Notary Public
 STATE CORPORATION COMMISSION

JAN 12 1996
 1-12-96
 COMMUNICATIONS DIVISION

