


STATE OF KANSAS
STATE CORPORATION COMMISSION

15051-00401-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ellis County. Sec 9 Twp. 13S Rge. 18W (E) (W)
Location as "NE/CNW/SW" or footage from lines SE SE SW
Lease Owner Alpine Oil & Royalty Co., Inc.
Lease Name Dreiling Well No. 1
Office Address 1100 Bitting Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 1, 1956 19
Application for plugging filed December 1, 1956 19
Application for plugging approved December 1, 1956 19
Plugging commenced December 1, 1956 19
Plugging completed December 1, 1956 19
Reason for abandonment of well or producing formation non productive



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3850 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 204' | Cemented |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy Mud from Total Depth, 3850 feet, to 200 feet,
1/2 sack hulls and plug, 20 sacks cement mud to
41 feet, 1/2 sack hulls and another plug and 10
sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Quaker Drilling Co., Inc.
Address 1100 Bitting Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Thomas M. McCaul (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas M. McCaul
1100 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of December, 1956

My commission expires August 10, 1957

Luzina Needell
Notary Public.

PLUGGING
FILE SEC 9 T 31 R 18W
BOOK PAGE 131 LINE 38

RECEIVED
STATE CORPORATION COMMISSION
DEC 4 - 1956
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: November 21, 1956

QUAKER DRILLING CO., INC., Contractor

Completed: December 1, 1956

Drilling No. 1
SE SE SW Sec. 9-13S-18W
Ellis County, Kansas

Elevation: 2170 K. B.

Production: D & A

Casing Record:

Set 204 feet of 8 5/8 inch casing with 150 sacks pozmix

15.051.00401.00.00

(Figures Indicate the Bottom of Formations)

| <u>FORMATIONS</u> | <u>DEPTH</u> | <u>FORMATION TOPS</u> | |
|-----------------------------------|--------------|-----------------------|------------|
| Surface Soil, Shale & Lime Shells | 204 | Anhydrite | 1462 |
| Shale & Shells | 500 | Heebner | 3435 -1265 |
| Shale and Sand | 554 | Toronto | 3456 -1286 |
| Shale and Shells | 870 | Lansing | 3482 -1312 |
| Shale | 920 | Conglomerate | 3740 -1570 |
| Sand | 1100 | Arbuckle | 3805 -1635 |
| Shale & Red Bed | 1360 | Rotary Total | |
| Shale | 1462 | Depth | 3850 -1680 |
| Anhydrite | 1500 | | |
| Shale & Shells | 2355 | | |
| Sandy Lime & Shale | 2425 | | |
| Lime & Shale | 2605 | | |
| Shale | 2900 | | |
| Shale & Lime | 3520 | | |
| Lime | 3720 | | |
| Shale & Lime | 3810 | | |
| Lime | 3850 | | |

We hereby certify the foregoing is a true and correct copy of the Driller's Log of the well drilled in the SE SE SW of Section 9, Township 13 South, Range 18 West, Ellis County, Kansas.

QUAKER DRILLING CO., INC.

By: Thomas M. McCaul
Thomas M. McCaul, President

~~SUBSCRIBED AND SWORN TO before me, a Notary Public, this 3rd day of December, 1956.~~



Virginia Merrill
Notary Public

MY COMMISSION EXPIRES:
August 10, 1957

PLUGGING
FILE SEC. 9 T. 31 R. 18W
BOOK PAGE 121 LINE 38

RECEIVED
REGISTRATION COMMISSION
DEC 4 - 1956
CONSERVATION DIVISION
Wichita, Kansas