

15-051-20936-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

~~15-051-20936-00-00~~
WELL PLUGGING RECORD

Ellis County, Sec. 9 Twp. 13 Rge. 18 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SE SE SE

Lease Owner Shields Oil Producers, Inc.

Lease Name Fellers "B" Well No. 1

Office Address Shields Bldg., Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 2-8 19 74

Application for plugging filed 2-8 19 74

Application for plugging approved 2-8 19 74

Plugging commenced 2-8 19 74

Plugging completed 2-8 19 74

Reason for abandonment of well or producing formation Dry hole


If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Depth to top Bottom Total Depth of Well 3,490' Feet

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	282'	Cmtd w/ 150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill hole w/ heavy mud
Push bridge plug to 500'
Spotted 50 sax cement on plug thru 4 1/2" drill pipe
Fill hole w/ heavy mud
Push bridge plug to 250'
Spotted 25 sax cement on plug thru 4 1/2" drill pipe
Push bridge plug to 40' w/ 1/2 sax hulls on plug
Dump 10 sax cement on plug to cellar

RECEIVED
STATE CORPORATION COMMISSION

MAR 1 1974
3-1-74
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shields Drilling Co., Inc.
Address Shields Bldg., Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.

R. L. Shields (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. L. Shields, pres.
Shields Bldg., Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 28th day of February, 1974

Ruth Phillips
Notary Public.

My commission expires May 26, 1975






Shields

Russell, Kansas

WELL LOG

Operator: Shields Oil Producers, Inc.
 Well: Fellers "B" #1
 Commenced: February 2, 1974
 Completed: February 8, 1974
 Contractor: Shields Drilling Co., Inc.

Well Description: SE SE SE
 Sec. 9-13S-18W
 Ellis Co., Kansas



CASING RECORD		
Size	Run	Pulled
8 5/8"	282'	Cmtd w/ 150 sax

Elevation: 2, 120' RB

Treatment:

Production: D & A

Tops: •

..... Figures Indicate Bottom of Formations . . . 15051:20936:00.00 . . .

Top soil, clay & post rock	40'
Shale	290'
Shale & redbed	600'
Shale	840'
Sand & shale	1,060'
Redbed & shale	1,401'
Anhydrite	1,440'
Redbed & shale	1,950'
Shale & lime	3,179'
Lime	3,490' RTD

RECEIVED
 STATE CORPORATION COMMISSION

MAR 1 1974

CONSERVATION DIVISION
 Wichita, Kansas

Notes