


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

15051-02782-00-00
WELL PLUGGING RECORD

Ellis County, Sec. 28 Twp. 13 Rge. 17W (EX) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW NE SW
Lease Owner Glenn R. Nye et al
Lease Name Drelling "B" Well No. 3
Office Address Hays, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed Oct. 30, 1953 19
Application for plugging filed Oct. 23, 1955 19
Application for plugging approved Oct. 31, 1955 19
Plugging commenced Oct. 26, 1955 19
Plugging completed Oct. 28, 1955 19
Reason for abandonment of well or producing formation depleted



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production Oct. 13, 1955 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Arbuckle dolomite Depth to top 3520 Bottom 3600 Total Depth of Well 3600 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface				8-5/8	103	cemented 75 sacks
				5 1/2"	3599'	M 2893'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed; from _____ feet to _____ feet for each plug set.

(Plug back depth 3552' - perforations at 3538-44)
Plugged hole to 3527' with crushed rock, and 4 sacks of cement.
Shot off 5 1/2" casing at 2893' and pulled casing.
Mixed and pumped 30 sacks Aqua-Jell mud into hole, put in plug and mixed and pumped 70 sacks of cement into hole.
Pumping pressure of cement: approximately 300 PSI.
Hole full of cement to within 5' of surface.

RECEIVED
STATE CORPORATION COMMISSION

NOV 9 1955
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Glenn R. Nye
Address Hays, Kansas

STATE OF Kansas, COUNTY OF Ellis, ss.

E. DeWitt Doley (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *E. DeWitt Doley*
Hays, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 5th day of November 1955

My commission expires May 9, 1957

John L. Spiess
Notary Public.

PLUGGING
FILE SEC-28-T-13 R7W
BOOK PAGE 12 LINE 5

Company: Glenn R. Nye et al
Contractor: Glenn R. Nye Drilling Co.
Commenced: October 20, 1953
Completed: October 30, 1953

Farm: Sophia Dreiling "B" 3
Location: SW NE SW Sec. 28-13-17
Ellis County, Kansas
Casing Record: 8 5/8" set at 103'
5 1/2" set at 3599
Elevation: 1995'

15.051.02782.00.00

(figures below indicate bottoms)

shale	104
shale	320
sand	380
shale-gumbo-sand	670
sand & shale	730
sand	850
shale & red bed	1100
shale & red bed	1209
anhydrite	1244
red bed & shale	1375
shale & shells	1620
shale & salt	1742
shale & salt	1825
shale & lime streaks	1955
shale & lime	1965
shale & lime	2150
lime & shale	2255
lime & shale	2355
lime & shale	2460
lime & shale	2585
shale & lime	2700
shale & lime	2806
shale & lime	2930
shale & lime	3040
shale & lime	3114
lime & shale	3169
lime & shale	3235
heebner	3237 Heebner (-1233)
lime & shale	3288
lime & shale	3353
K.C. lime	3395
lime	3442
lime	3495
lime & shale	3563
lime & shale	3600 T.D.

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

GLENN R. NYE DRILLING COMPANY

By Earl Justusbaum

STATE OF KANSAS)
) SS
ELLIS COUNTY)

Subscribed to and sworn to before me, a notary public, in and for said County and State this 20th day of Nov, 1953.

John L. Spies
Notary Public

My Commission Expires May 9, 1957

