


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

County. Sec. 28 Twp. 13 Rge. 17 (E) (W)  
Location as "NE/CNW/SW" or footage from lines NE SE SW  
Lease Owner Leo J. Dreiling ET AL  
Lease Name Sophia Dreiling Well No. E-1  
Office Address Victoria, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed January 21 19 54  
Application for plugging filed January 21 19 54  
Application for plugging approved January 21 19 54  
Plugging commenced January 21 19 54  
Plugging completed January 21 19 54  
Reason for abandonment of well or producing formation dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3580 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	12 1/4'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with drilling mud, set first plug at 120' with 1/3 sack hulls and 15 sacks cement, mudded to 41', set second plug at 41' with 1/2 sack hulls and 10 sacks cement, cement filled to bottom of cellar.

STATE CORPORATION COMMISSION  
FEB 19 1954  
CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Nye & Snell Drilling Company  
Address Drawer 30, Hays, Kansas

STATE OF Kansas, COUNTY OF Ellis, ss.  
Earl Quattlebaum (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl Quattlebaum

(Address) \_\_\_\_\_, 19 54

John L. Spiess  
Notary Public.



SUBSCRIBED AND SWORN to before me this 29th day of January, 19 54

My commission expires May 9, 1957

24-7366-5 3-53-20M

**PLUGGING**  
FILE SEC 28 T 13 R 17W  
BOOK PAGE 9 LINE 40

STATE CORPORATION COMMISSION  
FEB 18 1954  
Secretary

Company: Leo J. Dreiling  
 Contractor: Nye & Snell Drilling Company  
 Commenced: January 12, 1954  
 Completed: January 21, 1954

Farm: Sophia Dreiling "E"-1  
 Location: NE SE SW Sec. 28-13-17W  
 Ellis County, Kansas  
 Casing Record: 8 5/8" set @ 124'  
 Dry and Abandoned  
 Elevation: 2014 R.B.

15,051.04597.00 00

(figures below indicate bottoms)

surf clay	45
clay & gumbo	95
shale	125
shale	370
sand & shale	395
shale & shells	510
shale & shells	540
shale & sand streaks & gumbo	632
iron & shale	638
shale & iron streaks	670
sand	875
shale & red bed	1128
red bed & shale	1230
anhydrite	1266
red bed & shale & iron	1400
shale & shells & salt	1823
shale & salt	1890
shale & lime streaks	1976
shale & lime	2023
shale & lime	2200
lime & shale	2305
lime & shale	2405
lime & shale	2511
lime & shale	2641
shale & lime	2735
shale & lime	2817
lime & shale	2922
shale & lime	3052
shale & lime	3112
lime & shale	3192
lime & shale	3260
lime & shale	3263
shale(Heebner)	3267
lime & shale	3294
lime & shale	3300
K.C. lime & shale	3380
K.C. lime & shale	3450
lime & shale	3500
lime & shale	3534
lime & shale	3575
lime & shale	3580 T.D.

**PLUGGING**

FILE SEC    T    R     
 BOOK PAGE    LINE   

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

NYE & SNELL DRILLING COMPANY

By Earl Zuttbauer

STATE OF KANSAS )  
 ELLIS COUNTY )

ss

Subscribed to and sworn to before me, a notary public, in and for said County and State this 29th day of Jan 1954.

John L. Spiess  
 Notary Public

My Commission Expires May 9, 1957

**PLUGGING**  
 FILE SEC 28 T 13 R 17W  
 BOOK PAGE 9 LINE 40