

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

15-051-04290-00-00
WELL PLUGGING RECORD

Ellis County, Sec. 28 Twp. 13 Rge. 17W (W)

Location as "NE/CNW/SW" or footage from lines CNW NE.
Lease Owner Glenn R. Nye
Lease Name Bissing Well No. 4
Office Address Hays, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Nye & Snell
Date well completed Feb. 4, 1955 19
Application for plugging filed Feb. 4, 1955 19
Application for plugging approved Feb. 4, 1955 19
Plugging commenced Feb. 4, 1955 19
Plugging completed Feb. 5, 1955 19
Reason for abandonment of well or producing formation dry hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation none Depth to top Bottom Total Depth of Well 3592 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface				8-5/8"	123 ft	cemented 75 sacks
						(cement-circulated)

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set 8-5/8" plug at 120ft.
Put 1/2 sack hulls on plug and put 15 sacks of cement on hulls through drill pipe.
Filled hole with heavy mud to 40 ft.
Set 8-5/8" plug at 40 feet.
Put 1/2 sack hulls on plug.
Filled hole up to cellar with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Nye & Snell
Address Hays, Kansas

STATE OF Kansas, COUNTY OF Ellis, ss.

E. Dewitt Doley (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. Dewitt Doley

(Address)


SUBSCRIBED AND SWORN to before me this 5th day of February, 1955

John L. Spiess

Notary Public.

My commission expires May 9, 1957

24-7368-5 3-53-20M



2-11-55

Company: Glenn R. Nye Drilling Company
 Contractor: Nye & Snell Drilling Company
 Commenced: January 25, 1955
 Completed: February 3, 1955
 Elevation: 2005 K.B.

Farm: K. Bissing #4
 Location: C ~~S~~ 2 NW NW 28-13-17W
 Ellis County, Kansas
 Casing Record: 8 5/8" set at 123'
 Dry and abandoned.

15-051-04290-0000

(figures below indicate bottoms)

shale and sand	123
shale and sand	460
shale and sand and redbed	1218
anhydrite	1235
anhydrite	1254
shale, red	1515
salt, shale and shells	1885
shale and lime	2035
shale and lime	2160
shale and lime	2270
shale and lime	2355
shale and lime	2380
shale and lime	2455
shale and lime	2600
shale and lime	2700
shale and lime	2805
shale and lime	2940
shale and lime	3060
shale and lime	3125
shale and lime	3170
shale and lime	3230
shale and lime	3280
shale and lime	3328
shale and lime	3390
shale and lime	3460
shale and lime	3525
conglomerate	3592 T. D.

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

Nye & Snell Drilling Company

By *DeWitt Coley*

STATE OF KANSAS)
) SS
 ELLIS COUNTY)

Subscribed and sworn to before me, a Notary Public, in and for said County and State this 9th day of February, 1955.



John L. Spiess
 Notary Public

My Commission Expires May 9, 1957.

PLUGGING
 FILE NO. 28-13 R 124
 BOOK PAGE 95 LINE 39