


STATE CORPORATION COMMISSION

Give All Information Completely
 Make Required Affidavit
 Mail or Deliver Report to:
 Conservation Division
 State Corporation Commission
 211 No. Broadway
 Wichita, Kansas

15.051.01040.00.00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Ellis County. Sec. 28 Twp. 13 Rge. 17 (E) (W) X
 Location as "NE/CNW&SW&" or footage from lines SE SE NE
 Lease Owner Leo J. Dreiling Oil Company
 Lease Name Dreiling "H" Well No. 1
 Office Address Victoria, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) D. & A.
 Date well completed February 28, 1962 19
 Application for plugging filed February 28, 1962 19
 Application for plugging approved February 28, 1962 19
 Plugging commenced February 28, 1962 19
 Plugging completed February 28, 1962 19
 Reason for abandonment of well or producing formation -0-

If a producing well is abandoned, date of last production -0- 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
 Producing formation -0- Depth to top -0- Bottom -0- Total Depth of Well 3555' Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8-5/8"	126'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Rotary mud was used to fill hole to a depth of 480' were 1st plug was set using 20 sacks cement, 2nd plug was set at 180' using 20 sacks of cement, 3rd plug was set at 40' using 10 sacks cement and filling to top of hole.

RECEIVED
 STATE CORPORATION COMMISSION
 APR 23 1962
 4-23-62
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. DREILING & SONS, INC.
 Address VICTORIA, KANSAS

STATE OF KANSAS, COUNTY OF ELLIS, ss.

I, Leo F. Dreiling a partner (employee of owner or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling
Leo F. Dreiling
Victoria, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 28th day of February, 19 62

My commission expires August 14, 1965

Ronald Zimmerman
 Notary Public.



L. J. DREILING and SONS, Inc.

VICTORIA, KANSAS

WELL LOG

15051010400000

Company Leo J. Dreiling Oil Company
Victoria, Kansas

Sec. 28 Twp. 13 Rng. 17W

Farm Dreiling "H" No. 1

Location SE SE NE

Total Depth 3555'

County Ellis County, Kansas

Comm. 2-21-62 Comp. 2-28-62

Elevation: D. F.

Contractor L. J. DREILING & SONS, INC.
VICTORIA, KANSAS

G. R. 1955'

Casing Record
126' - - - 3 5/8"

Cement Record
65 sacks cement

Production:
D & A

Figures Indicate Bottom of Formations

0 - 49	Surface Clay
49 - 102	Surface Clay & Shale
102 - 126	Shale
126 - 1090	Shale & Shells
1090 - 1173	Shale
1173 - 1200	Anhydrite
1200 - 1515	Shale & Shells
1515 - 1915	Shale
1915 - 2161	Shale & Lime
2161 - 2285	Lime & Shale
2285 - 2458	Lime & Shale
2458 - 2715	Shale & Lime
2715 - 2885	Shale & Broken Lime Streaks
2885 - 3080	Shale & Lime
3080 - 3170	Lime
3170 - 3265	Lime
3265 - 3380	Lime
3380 - 3470	Lime
3470 - 3502	Lime
3502 - 3515	Lime
3515 - 3528	Lime
3528 - 3555	Arbuckle
3555	TD

STATE OF KANSAS
STATE COMMISSION
MAY 2 1962
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss.
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy of the log from the Daily Drilling Report on your Dreiling "H" No. 1.

Leo F. Dreiling
LEO F. DREILING

Subscribed and sworn to before me this 28th day of February, 1962

Robert Zimmerman
NOTARY PUBLIC

My Commission Expires: August 14, 1965