



DRILLING LOG

Weber No. 1 - NE NE SW of Sec. 28, T. 13 S., R. 17 W.,  
Ellis County, Kansas

DRILLED FOR: H. A. HERSHFELD & CO., INC., ET AL.  
DRILLED BY: THE WESTERN DRILLING CO., INC.

COMMENCED: 9/18/46  
COMPLETED DRILLING W/ROTARY: 10/8/1946

15-051-04840-00-00

Clay and Surface	90
Blue Shale	140
Shale and Shells	215
Shale & Shells	525
Shale & Shells	660
Sand & Shells	855
Shale	875
Shale & Shells	1085
Red Rock & Shale	1180
Broken Lime	1190
Anhydrite	1235
Lime	1250
Red Rock Shale & Salt	1445
Broken Lime	1485
Broken Lime	1535
Shale & Shells	1665
Shale & Lime Shells	1862
Lime & Shale	1970
Lime & Shale	2080
Lime & Shale	2150
Lime	2175
Lime	2230
Lime	2275
Lime	2320
Lime Broken	2380
Lime & Shale	2445
Lime & Shale	2495
Shale & Lime	2558
Lime & Shale	2640
Broken Lime Shale	2725
Broken Lime & Shale	2830
Lime	2835
Shale	2840
Lime	2890
Lime & Shale	2965
Sand and Gravel	2970
Lime and Gumbo	3030
Lime	3055
Lime & Chert	3105
Lime	3135
Lime	3151
Lime	3180
Lime	3225
Lime	3299
Lime	3359
Lime	3371
Total Depth	3371

10-3/4" Surface Casing 140' Cemented with 100 Sacks  
5 1/2" (Derrick Floor) 3360' - Cemented with 75 Sacks\*

\*Drilling Report says 75 Sacks  
Halliburton Report says 100 Sacks.

28 13 17w  
111 11