

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-24,770

LEASE NAME Dreiling

WELL NUMBER #2

SPOT LOCATION SW-SE-NE

SEC. 28 TWP. 13S RGE. 17W (E) or (W)

COUNTY Ellis

Date Well Completed 11/18/91

Plugging Commenced 11/18/91

Plugging Completed 11/18/91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR S.B. Oil

ADDRESS 3204 Willow, Hays, KS 67601

PHONE # (913) 628-4547 OPERATORS LICENSE NO. 3715

Character of Well D & A
(Oil, Gas, D&A, SMD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, KS

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION
12-6-91
DEC 6 1991

Formation	Content	From	To	Size	Put in	Plugged

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Pumped 100 sacks @ 1555' with 60/40 poz. 3% cc, 1/2# floseal per sack. Pumped @ 1245' another 100 sacks 60/40 poz., 3% cc, 10% gilsonite, 1/4# floseal per sack.

A solid bridge was set at 860'. Plugged with additional 200 sacks 60/40 poz 8% gel, 1/2# floseal per sack, 165 sacks @ 860' circulate to surface. Wiper plug @ 40' with 10 sacks to surf., 10 sacks in mousehole, 15 sacks in bathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. _____
Address Russell, KS 67665

STATE OF _____ COUNTY OF _____, ss.

(employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

NOTARY PUBLIC - State of Kansas
LINDA K. BIXENMAN
My Appt. Exp. 6/21/95

(Signature) [Signature]
(Address) 3204 Willow Hays 67601

SUBSCRIBED AND SWORN TO before me this 3rd day of January, 1991

Linda K. Bixenman
Notary Public

My Commission expires: 6-21-95