

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-051-04837-00-00

API NUMBER 11-28-46

LEASE NAME Dreiling C

WELL NUMBER 1

 Ft. from S Section Line

SW NE $\frac{1}{4}$ Ft. from E Section Line

SEC. 28 TWP. 13 RGE. 17 (E) of (W)

COUNTY Ellis

Date Well Completed 11-28-46

Plugging Commenced 5-28-91

Plugging Completed 5-28-91

TYPE OR PRINT

NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Berexco, Inc.

ADDRESS Box 723 Hays, Kansas 67601

PHONE# (913) 628 6101 OPERATORS LICENSE NO. 5363

Character of Well Oil

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on 5-28-91 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? if not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3265

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled
	Surface	0	117	10 3/4"		None
	Casing	0	3257	5 1/2"		None

RECEIVED

STATE CORPORATION COMMISSION
5-30-91
 MAY 30 1991
 CONSERVATION DIVISION
 Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Run 2 shots to 1210'. Stopped at 600'. Perf. at 500'. Run tubing openended to 1199'. Run 2 shots in tubing to 1210'. Run tubing to 3030'. Mix and spot 100 sk. 65/35 8% gel. Pull tbg. to 1800'. Mix and spot 100 sk. 65/35 8% gel. Pull tubg. to 600'. Mix and circ. 40 sk. to top. Hook up to 10 3/4 mix and pump cement pressure to 400# ST. Hook to 5 1/2 and mix and squeeze
 (If additional description is necessary, use BACK of this form.)

50 sk. and 50# hulls. Max. pressure 750#. Used 300 sks. total.

Name of Plugging Contractor Berexco, Inc. License No. 5363

Address Box 723 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford


(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ted Crawford

(Address) Box 723 Hays, Mo 67601

Sworn to before me this 29 day of May, 19 91

Rosemary Smith
 Notary Public



My Commission Expires: May 1, 1995