

TO:  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING  
 130 SOUTH MARKET, SUITE 2078  
 WICHITA, KANSAS 67202

API Well Number: 15-051-04869-00-00  
 Spot: NWNWSE Sec/Twnshp/Rge: 21-11S-18W  
2273 feet from S Section Line, 2422 feet from E Section Line  
 Lease Name: WASINGER Well #: 8  
 County: ELLIS Total Vertical Depth: 3546 feet

Operator License No.: 3553  
 Op Name: CITATION OIL & GAS CORP.  
 Address: 14077 CUTTEN RD PO BOX 690688  
HOUSTON, TX 77269

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3160		
CIBP		3326		
CIBP		3370		
CIBP		3398		
SURF	8.625	1265	0	600 SX
PROD	5.5	3546	0	200 SX

Well Type: EOR UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/18/2011 9:00 AM  
 Plug Co. License No.: 34147 Plug Co. Name: ACE WELL SERVICE, INC.  
 Proposal Rcvd. from: NEIL PFANNENSTIEL Company: CITATION OIL & GAS CORP. Phone: (785) 798-5637

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls - 12 sxs gel. PBTD 2160'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
 Date/Time Plugging Completed: 04/18/2011 1:00 PM KCC Agent: PAT STAAB

**Actual Plugging Report:**

Log Tech set CIBP at 2900' - covered with 2 sxs cement.  
 Log Tech perfed at 1750' - 1280'.  
 Ace Well Service RIH with tubing to 2850'. Allied rigged to tubing and pumped 12 sxs gel - followed with 10 sxs cement.  
 Pulled tubing to 1750'. Allied rigged to tubing and mixed and pumped 40 sxs cement with 100# hulls mixed in.  
 Pulled tubing to 1250' - mixed and pumped 120 sxs cement to circulate cement to pit area.  
 Pulled tubing. Topped 5 1/2" casing with 15 sxs - hole standing full.  
 Rigged to 8 5/8" casing and pumped 10 sxs cement.  
 Max. P.S.I. 300#. S.I.P. 300#.

Note: Possible being carried under Injection Number: E-10,120.

**Perfs:**

Top	Bot	Thru	Comments
3514	3530		ARBUCKLE
3368	3374		LKC 'I'
3288	3298		LKC 'G'
3245	3250		LKC 'B'
3192	3196		TORONTO
3132	3138		TOPEKA 'D'
3074	3078		TOPEKA 'D'
2974	2977		TOPEKA 'D'


RECEIVED  
 APR 22 2011  
 KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #039591.

Plugged through: TBG

District: 04

Signed

  
 (TECHNICIAN)

CM

APR 19 2011

Form CP-2/3

4/25