

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-01352-00-00  
Spot: SWNWNWNW Sec/Twnshp/Rge: 20-11S-17W  
330 feet from N Section Line, 330 feet from W Section Line  
Lease Name: HADLEY D Well #: 2  
County: ELLIS Total Vertical Depth: 3615 feet

Operator License No.: 33979  
Op Name: CLIPPER ENERGY LLC C/O VESS OIL  
Address: 1700 WATERFRONT PKWY, BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	389	0	175 SX
PROD	5.5	3593	0	100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/18/2011 1:00 PM  
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE  
Proposal Rcvd. from: JOEL STULL Company: VESS OIL COMPANY Phone: (785) 885-4240

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 500# hulls.  
Started at zero feet - worked 14 days to drill to 1892'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/18/2011 3:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perfed at 1350' - ticket #819.  
Smoky Hills Well Service RIH with tubing to 1856'.  
Allied rigged to tubing and pumped 100 sxs cement.  
Pulled tubing to 921'. Allied rigged to tubing and pumped 100 sxs cement to circulate cement to surface.  
Pulled tubing. Rigged to 5 1/2" casing with a swedge and pumped 30 sxs cement.  
Max. P.S.I. 300#. S.I.P. 100#.  
Rigged to 8 5/8" casing and pumped 25 sxs cement.  
Max. P.S.I. 300#. S.I.P. 100#.

Perfs:


Top	Bot	Thru	Comments
3593	3615		ARBUCKLE OHIO
3351	3495		LKC
387	740		100 SX

Remarks: ALLIED CEMENTING COMPANY-TICKET #39678.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

RECEIVED  
APR 22 2011

KCC WICHITA

APR 19 2011

Form CP-2/3

✓ 4/25