

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-107-22503-00-01  
Spot: SENENENW Sec/Twnshp/Rge: 2-22S-22E  
4785 feet from S Section Line, 2840 feet from E Section Line  
Lease Name: LANHAM Well #: 3  
County: LINN Total Vertical Depth: 760 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	20		10 SX
PROD	4.5	759		80 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/24/2010 8:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: REX ASHLOCK Company: \_\_\_\_\_ Phone: (620) 365-3111

Proposed Plugging Method: 300' OF CEMENT AT BOTTOM OF E-LOG DEPTH NOTED ABOVE, "GEL" SPACER, CEMENT FROM 250' TO SURFACE. OK'D BY STEVE KORF, DISTRICT 3 OFFICE, CHANUTE, KS ON 11/22/2010.

Plugging Proposal Received By: LEVI SHORT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/24/2010 12:00 PM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 1-INCH TO 759 FEET IN 4-1/2 INCH AND PUMP 49 SACKS OF CEMENT TO 500 FEET. THEN PLACE 22 SACKS OF CEMENT FROM 250 FEET TO SURFACE. GEL SPACER WAS PLACED BETWEEN CEMENT PLUGS. HOOKED ON TO 4-1/2 INCH AND SQUEEZED 6 SACKS TO SURFACE TO SHUT IN WELL. USE TOTAL OF 71 SACKS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
700	726		BARTLESVILLE

RECEIVED

APR 13 2011 LS

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED

APR 18 2011

KCC WICHITA

Form CP-2/3

4/25