

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-107-21607-00-00  
Spot: SWSWSESW Sec/Twnshp/Rge: 35-21S-22E  
196 feet from S Section Line, 3840 feet from E Section Line  
Lease Name: LANHAM TEXOKAN Well #: 1  
County: LINN Total Vertical Depth: 989 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	20		10 SX
T1	2.375	690		
PROD	4.5	877		80 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/23/2010 2:30 PM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: REX ASHLOCK Company: \_\_\_\_\_ Phone: (620) 365-3111

Proposed Plugging Method: 300' OF CEMENT AT 861 (TD REACHED BY GR-N E LOG) THEN A "GEL" SPACER, AND CEMENT FROM 250' TO SURFACE. OK'D BY STEVE KORF, DISTRICT 3 OFFICE, CHANUTE, KS ON 11/22/10.

Plugging Proposal Received By: LEVI SHORT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/23/2010 5:00 PM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 1-INCH TO 877 FEET IN 4-1/2 INCH AND PUMP 25 SACKS OF CEMENT TO 500 FEET. THEN PLACE 34 SACKS OF CEMENT FROM 250 FEET TO SURFACE. GEL SPACER WAS PLACED BETWEEN CEMENT PLUGS. USE TOTAL OF 59 SACKS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
700	705		BARTLESVILLE

RECEIVED

APR 13 2011

LS

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED Form CP-2/3  
APR 18 2011 4/25  
KCC WICHITA