

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-20315-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 12-13S-22W
3630 feet from S Section Line, 2310 feet from E Section Line
Lease Name: HERL Well #: 2
County: TREGO Total Vertical Depth: 3410 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 1019
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	217	0	160 SX
PROD	4.5	3894	0	175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/12/2011 8:30 AM
Plug Co. License No.: 31720 Plug Co. Name: STEWART WELL SERVICE INC
Proposal Rcvd. from: TERRY W. PIESKER Company: DOWNING-NELSON OIL CO INC Phone: (785) 621-2610

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 400# hulls.
CIBP at 3410'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/12/2011 12:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3378' - pumped 100 sxs cement with 250# hulls.
Pulled tubing to 1900' - pumped 150 sxs cement - good circulation of cement.
Pulled tubing out - topped off with 20 sxs cement - full.
Tied onto backside - pumped 5 sxs cement.
S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3742	3750		
3725	3732		
3705	3710		
3663	3672		
3640	3644		
3623	3629		
3605	3611		

RECEIVED
APR 18 2011
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed *Marvin Mills*
(TECHNICIAN) CM

Form CP-2/3

✓ 4/25

APR 14 2011