

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-165-21839-00-00  
Spot: NWSWSESW Sec/Twnshp/Rge: 20-18S-19W  
564 feet from S Section Line, 1484 feet from W Section Line  
Lease Name: FELDER Well #: 1-20  
County: RUSH Total Vertical Depth: 4160 feet

Operator License No.: 9855  
Op Name: GRAND MESA OPERATING COMPANY  
Address: 1700 N WATERFRONT PKWY BLDG 600  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1252		WITH 450 SX CMT
PROD	5.5	4160	2240	WITH 175 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/25/2011 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 200# HULLS & 30 SX CMT THRU PERFS. PLUG AT 1280' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/25/2011 11:00 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMP 200# HULLS & 30 SX CMT. 1ST PLUG AT 1290' WITH 15 SX GEL - 50 SX CMT - & 100# HULLS. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3958	3960		CHEROKEE SAND
3950	3952		CHEROKEE SAND

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

RECEIVED  
APR 19 2011

KCC WICHITA

District: 01

Signed

*Michael Maier*  
(TECHNICIAN)

RECEIVED

APR - 5 2011

KCC DODGE CITY

Form P-2/3  
4/25