

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-23550-00-00  
Spot: S2NESWSE Sec/Twnshp/Rge: 27-14S-15W  
970 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: NUSS Well #: 1  
County: RUSSELL Total Vertical Depth: 3360 feet

Operator License No.: 33813  
Op Name: JASON OIL COMPANY, LLC  
Address: 3718- 83RD ST PO BOX 701  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	466	0	220 SX CMT
T1	2.875	3304		
PROD	5.5	3359	1905	150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/05/2011 9:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: DAVID FUNK Company: JASON OIL COMPANY, LLC Phone: (785) 483-2025

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 600# hulls.  
Cut casing at 1905' - 46 joints out of the hole.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/05/2011 1:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

04/04/2011 - Sanded off bottom and spotted 5 sxs cement on top.  
04/05/2011 - Cut casing at 1905'.  
Pulled casing to 1705' - pumped 150 sxs cement with 300# hulls.  
Pulled casing to 975' - pumped 25 sxs cement.  
Pulled casing to 505' - pumped 100 sxs cement with 200# hulls.  
Pulled casing to 80' - pumped 25 sxs cement - circulated.  
POOH. Topped off with 5 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3304	3306		
3146	3150		
3082	3086		

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #5027.

Plugged through: CSG

District: 04

Signed Ray A Dinkel

(TECHNICIAN) RECEIVED CM

APR 15 2011 Form CP-2/3

KCC WICHITA 4/25

APR 12 2011