

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23577-00-00
Spot: N2NWSWSE Sec/Twnshp/Rge: 27-14S-15W
1010 feet from S Section Line, 2310 feet from E Section Line
Lease Name: NUSS Well #: 2
County: RUSSELL Total Vertical Depth: 3298 feet

Operator License No.: 33813
Op Name: JASON OIL COMPANY, LLC
Address: 3718- 83RD ST PO BOX 701
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	482	0	220 SX
TI	2.5	3293		
PROD	5.5	3295	2327	120 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/08/2011 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: DAVE FUNK Company: JASON OIL COMPANY, LLC Phone: (785) 483-2025

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 600# hulls.
04/07/2011 - Sanded off bottom to 2950' and spotted 5 sxs cement on top.
Cut casing at 2327'.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/08/2011 1:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Cut casing at 2327'.
Pulled casing to 1502' - pumped 100 sxs cement with 300# hulls.
Pulled casing to 975' - pumped 25 sxs cement.
Pulled casing to 505' - pumped 100 sxs cement with 150# hulls - cement circulated.
POOH. Topped off with 25 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3298	3304		OPEN HOLE

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4522.

Plugged through: CSG

District: 04

Signed Ray A. Dinkel

(TECHNICIAN)

RECEIVED

APR 15 2011

KCC WICHITA

Form CP-2/3

CM

4/25

APR 12 2011