

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01940-00-00
Spot: W2NENENW Sec/Twnshp/Rge: 18-10S-19W
4956 feet from S Section Line, 3133 feet from E Section Line
Lease Name: ANDERSON Well #: 3
County: ROOKS Total Vertical Depth: 3876 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 S MARKET ST
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3777		
SURF	10.75	256	0	150 SX
PROD	7	3861	0	250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/07/2011 9:00 AM
Plug Co. License No.: 34410 Plug Co. Name: AMERICAN PULLING SERVICE
Proposal Rcvd. from: DAVID JENSEN Company: LARIO OIL & GAS COMPANY Phone: (785) 259-1778

Proposed Plugging Method: Ordered 525 sxs 60/40 pozmix - 4% gel - 800# hulls - 17 sxs gel.
Log Tech perfed at 2050' - 1667' - 1000' - 225'.
Squeezed casing at 1502' - 1533' w/100 sxs.
PBTB 3745'. Tools in the hole below PBTB.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/07/2011 2:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

American Pulling Services RIH with tubing to 3589'.
Pumped 17 sxs gel - followed with 80 sxs 60/40 pozmix - 4% gel with 300# hulls.
Pulled tubing to 2032'. Allied rigged to tubing and mixed and pumped 150 sxs cement with 200# hulls.
Pulled tubing to 1112'. Allied rigged to tubing and mixed and pumped 185 sxs cement with 150# hulls to circulate cement up 7" casing.
Pulled tubing - rigged to 7" casing with a swedge and pumped 15 sxs cement.
Max. P.S.I. 400#. S.I.P. 400#.
Cement did not circulate up to 10 3/4" casing.
Operator will cut off and fill with ready mix if needed.


Perfs:

Top	Bot	Thru	Comments
3809	3814		
3795	3799		
3772	3777		
3678	3680		
3668	3670		
3662	3664		
3637	3641		
3623	3627		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed 
(TECHNICIAN)

RECEIVED

APR 15 2011 Form CP-2/3
4/25

KCC WICHITA

APR 11 2011