

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-24760-00-00
Spot: SWNENE Sec/Twnshp/Rge: 27-14S-16W
4290 feet from S Section Line, 990 feet from E Section Line
Lease Name: SCHRANT Well #: 2
County: ELLIS Total Vertical Depth: 3474 feet

Operator License No.: 30737
Op Name: M.A. YOST OPERATIONS, INC
Address: 30 N BROOKS PO BOX 811
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	971	0	400 SX
PROD	5.5	3465	2050	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/12/2011 3:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 257-2719

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/12/2011 5:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with a dump bailer and sanded off bottom of well to 3342' - dumped 5 sxs cement.
Cut off 5 1/2" casing at 2050'.
Pulled to 1550' - rigged to 5 1/2" casing and mixed and pumped 125 sxs cement with 300# hulls mixed in.
Pulled casing to 1000' - mixed and pumped 40 sxs cement with 100# hulls mixed in.
Pulled casing to 450' - mixed and pumped 50 sxs cement with 100# hulls mixed in.
Pulled casing to 150' - rigged to casing and mixed and pumped 70 sxs cement to circulate cement to surface.
Pulled casing - hole standing full.

Perfs:

Top	Bot	Thru	Comments
3404	3407		ARBUCKLE

Remarks: QUALITY WELL SERVICE, INC.-TICKET #5179.

Plugged through: CSG

District: 04

Signed _____

(TECHNICIAN)

cm

RECEIVED

APR 15 2011

Form CP-2/3

KCC WICHITA

APR 13 2011