

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-22491-00-00  
Spot: NENENE Sec/Twnshp/Rge: 1-30S-12W  
4895 feet from S Section Line, 372 feet from E Section Line  
Lease Name: MARTIN Well #: 1  
County: BARBER Total Vertical Depth: 3845 feet

Operator License No.: 31881  
Op Name: MCGINNESS OIL COMPANY OF KANSA  
Address: 1551 N WATERFRONT PKWY STE 150  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2900		WITH 2 SX CMT
SURF	8.625	351		WITH 200 SX CMT
PROD	4.5	3387	2150	WITH 175 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/04/2011 9:00 AM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 2900' & 2 SX CMT. PLUG AT 740' WITH 10 SX GEL & 50 SX CMT. PLUG AT 380' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/04/2011 10:15 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 2900' & PUT 2 SX CMT ON TOP OF CIBP. 1ST PLUG AT 740' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 380' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3321	3327		
3177	3182		
2948	2953		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

RECEIVED  
APR 18 2011  
KCC WICHITA

District: 01

Signed Stephen J. Pfeifer  
(TECHNICIAN)

RECEIVED  
APR 11 2011  
KCC DODGE CITY

Form CP-24  
4/20