

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-20350-00-01
Spot: NWNESE Sec/Twnshp/Rge: 36-16S-29W
2358 feet from S Section Line, 789 feet from E Section Line
Lease Name: TERWILLIGER NE UNIT Well #: 4
County: LANE Total Vertical Depth: 4625 feet

Operator License No.: 5144
Op Name: MULL DRILLING COMPANY, INC.
Address: 1700 N WATERFRONT PKWY BLDG 12
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4138		
SURF	8.625	325		WITH 200 SX CMT
L1	4.5	4182		WITH 70 SX CMT
PC		2205		CMT TO SURFACE
PROD	5.5	4623	0	WITH 150 SX CMT

Well Type: EOR UIC Docket No: E27690.1 Date/Time to Plug: 04/01/2011 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: JERRY ROANE Company: MULL DRILLING Phone: (316) 264-6366

Proposed Plugging Method: CIBP @ 4138' WITH 2 SX CMT. SWAB CASING TO 2350' TIE ONTO CASING & FILL WITH CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/01/2011 11:00 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

CIBP @ 4138' & 2 SX CMT. SWAB CASING TO 2350' TIE ONTO CASING & PUMP 165 SX CMT. PRESSURED TO 1000#. SHUT IN WITH 1000#. TIED ONTO BACKSIDE & PUMPED 1/4 BBL. PRESSURED TO 500#.

Perfs:

Top	Bot	Thru	Comments
4419	4427		
4402	4410		
4393	4398		
4340	4345		
4278	4284		
4255	4259		

RECEIVED
APR 19 2011
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 YR** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED OIL WELL.

Plugged through: CSG

District: 01

RECEIVED
APR -5 2011
KCC DODGE CITY

Signed

Michael Maier

(TECHNICIAN)