

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21811-00-00
Spot: S2NWNE Sec/Twnshp/Rge: 21-7S-19W
4290 feet from S Section Line, 1980 feet from E Section Line
Lease Name: KOPPES Well #: 2-21
County: ROOKS Total Vertical Depth: 3442 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	206	0	130 SX
PROD	5.5	3407	0	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/06/2011 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: BRANDON SIROKY Company: OIL PRODUCERS INC. OF KANSAS Phone: (316) 215-1357

Proposed Plugging Method: Ordered 355 sxs 60/40 pozmix - 4% gel - 200# hulls - 9 sxs gel spacer.
Perforated at 200' - 900' - 1475' - 1900'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/06/2011 4:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3000' - pumped 9 sxs gel spacer - followed with 50 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 1900' - pumped 100 sxs 60/40 pozmix - 4% gel.
Pulled tubing to 1000' - pumped 115 sxs 60/40 pozmix - 4% gel to circulate to surface.
Pulled all tubing. Hooked to 5 1/2" casing - pumped 90 sxs 60/40 pozmix - 4% gel - circulated out of 8 5/8" x 5 1/2" annulus.
Closed annulus in and pressured to 250# S.I.P.

Perfs:

Top	Bot	Thru	Comments
3407	3442		
3330	3334		
3096	3104		

RECEIVED
APR 18 2011
KCC WICHITA

Remarks: QUALITY WELL SERVICE-TICKET #5175.

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

Form CP-2/3

✓ 4/25

APR 14 2011