

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23265-00-00
Spot: SWSESW Sec/Twnshp/Rge: 16-7S-19W
330 feet from S Section Line, 3630 feet from E Section Line
Lease Name: MUIR B Well #: 1
County: ROOKS Total Vertical Depth: 3531 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	247	0	145 SX
PROD	4.5	3530	0	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/07/2011 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: BRANDON SIROKY Company: OIL PRODUCERS INC. OF KANSAS Phone: (316) 215-1357

Proposed Plugging Method: Ordered 265 sxs 60/40 pozmix - 4% gel - 200# hulls - 6 sxs gel spacer.
Squeezed from 533' - 565' w/150 sxs.
Perforated at 240' - 1485' - 1900'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/07/2011 3:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3000' - pumped 6 sxs gel spacer - followed with 50 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 1900' - pumped 100 sxs 60/40 pozmix - 4% gel.
Pulled tubing to 1000' - pumped 80 sxs 60/40 pozmix - 4% gel to circulate to surface.
Pulled all tubing. Topped off 4 1/2" casing with 20 sxs 60/40 pozmix - 4% gel.
Hooked to 8 5/8" x 4 1/2" annulus - pumped 15 sxs 60/40 pozmix - 4% gel.
S.I.P. 150#.

Perfs:

Top	Bot	Thru	Comments
3451	3452		
3438	3441		
3346	3350		

Remarks: QUALITY WELL SERVICE-TICKET #5176.

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

RECEIVED
APR 18 2011
KCC WICHITA

Form CP-2/3

✓ 4/25

APR 14 2011