

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-21980-00-00  
Spot: NWNWSE Sec/Twnshp/Rge: 2-7S-20W  
2310 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: WILLS Well #: 1  
County: ROOKS Total Vertical Depth: 3650 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS INC. OF KANSAS  
Address: 1710 WATERFRONT PKWY  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	248	0	
PROD	4.5	3650	0	150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/08/2011 2:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: BRANDON SIROKY Company: OIL PRODUCERS INC. OF KANSAS Phone: (316) 215-1357

Proposed Plugging Method: Ordered 285 sxs 60/40 pozmix - 4% gel - 200# hulls - 8 sxs gel spacer.  
Perforated at 240' - 1030'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/08/2011 5:15 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3200' - pumped 8 sxs gel spacer - followed with 50 sxs 60/40 pozmix - 4% gel with 200# hulls.  
Pulled tubing to 1900' - pumped 100 sxs 60/40 pozmix - 4% gel.  
Pulled tubing to 1000' - pumped 75 sxs 60/40 pozmix - 4% gel to circulate to surface.  
Pulled all tubing. Hooked to 4 1/2" casing - pumped 60 sxs 60/40 pozmix - 4% gel - circulated out of the 8 5/8" x 4 1/2" annulus.

Perfs:

Top	Bot	Thru	Comments
3605	3610		
3588	3590		
3579	3586		
3522	3526		

Remarks: QUALITY WELL SERVICE-TICKET #5178.

Plugged through: TBG

RECEIVED  
APR 18 2011  
KCC WICHITA

District: 04

Signed \_\_\_\_\_

*Pat Bedore*

(TECHNICIAN)

CM

Form CP-2/3

✓ 4/25

APR 14 2011