

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-22370-00-00  
Spot: SWNWSNW Sec/Twnshp/Rge: 34-15S-21W  
1760 feet from N Section Line, 1400 feet from W Section Line  
Lease Name: SQUIER BENTEMAN Well #: 1-34  
County: TREGO Total Vertical Depth: 4323 feet

Operator License No.: 5086  
Op Name: PINTAIL PETROLEUM, LTD.  
Address: 225 N MARKET STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	224	0	160 SX CMT.
T1	2.375	4140		
PROD	5.5	4315	0	100 SX CMT.

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/13/2011 11:00 AM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: WHITETAIL CRUDE Company: PINTAIL PETROLEUM, LTD. Phone: (316) 263-2243

Proposed Plugging Method: Ordered 280 sxs 60/40 pozmix - 4% gel - 500# hulls - 19 sxs gel.  
PC at 1701' with 150 sxs cement.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/13/2011 2:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4185' - pumped 19 sxs gel - followed with 50 sxs cement and 100# hulls.  
Pulled tubing to 1800' - pumped 200 sxs cement with good circulation of cement.  
Pulled tubing out - filled with 10 sxs cement - full.  
Tied onto backside - pumped 85 sxs cement.  
S.I.P. 100#.

Perfs:


Top	Bot	Thru	Comments
4188	4192		FT SCOTT

Remarks: SWIFT CEMENTING COMPANY-TICKET #1945.

Plugged through: TBG

District: 04

Signed

  
(TECHNICIAN)

CM

RECEIVED  
APR 18 2011  
KCC WICHITA

Form CP-2/3

APR 14 2011