

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22459-00-00
Spot: SENE Sec/Twnshp/Rge: 27-15S-21W
3320 feet from S Section Line, 610 feet from E Section Line
Lease Name: UNREIN HM Well #: 1-27
County: TREGO Total Vertical Depth: 4310 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	218	0	160 SX CMT.
T1	2.375	4110		
PC		1720		150 SX SMD CMT
PROD	5.5	4306	0	200 SX CMT.

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/14/2011 2:00 PM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: WHITETAIL CRUDE Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls - 19 sxs gel.
PC at 1788' w/180 sxs cement.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/14/2011 4:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4185' - pumped 19 sxs gel - followed with 50 sxs cement.
Pulled tubing to 1800' - pumped 200 sxs cement.
Pulled tubing out. Topped off with 20 sxs cement - full.
Tied onto backside and pumped 20 sxs cement.
S.I.P. 400#.

Perfs:

Top	Bot	Thru	Comments
4158	4188		NATURAL

RECEIVED
APR 22 2011
KCC WICHITA

Remarks: SWIFT CEMENTING COMPANY-TICKET #19453.

Plugged through: TBG

District: 04

Signed Marvin Mills
(TECHNICIAN) CM

4/25