

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-057-20685-00-00
Spot: SENWSE Sec/Twnshp/Rge: 13-25S-23W
1576 feet from S Section Line, 1623 feet from E Section Line
Lease Name: INDIEK Well #: 13-10
County: FORD Total Vertical Depth: 5200 feet

Operator License No.: 32204
Op Name: REDLAND RESOURCES, INC.
Address: 6001 NW 23RD ST.
OKLAHOMA CITY, OK 73127

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4710		WITH 2 SX CMT
SURF	8.625	772		WITH 400 SX CMT
COND	20	70		WITH 9 YDS CMT
PROD	4.5	5007	2201	WITH 275 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/24/2011 9:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: DAVID HICKMAN Company: REDLAND RESOURCES Phone: (580) 334-7013

Proposed Plugging Method: CIBP @ 4710' WITH 2 SX CMT. PLUG AT 1560' WITH 15 SX GEL & 50 SX CMT. PLUG AT 810' WITH 50 SX CMT. PLUG AT 390' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/24/2011 11:30 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4710' WITH 2 SX CMT. 1ST PLUG AT 1560' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 810' WITH 50 SX CMT. 3RD PLUG AT 390' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. CMT CIRCULATED BUT FELL. TOPPED OFF WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4801	4805		
4788	4791		
4778	4780		
4772	4774		
4762	4769		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED

APR 12 2011

KCC DODGE CITY

Signed

Eric MacLaren

(TECHNICIAN)

RECEIVED
APR 18 2011

KCC WICHITA

Form CP-28
4/25