

Notice: Fill out COMPLETELY  
and return to Conservation Division at  
the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 33999  
Name: Linn Operating, Inc.  
Address 1: 600 Travis/Suite 5100  
Address 2: \_\_\_\_\_  
City: Houston State: TX Zip: 77002 + \_\_\_\_\_  
Contact Person: Rena Carter  
Phone: ( 405 ) 241-2223  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
Mississippi Depth to Top: 4200 Bottom: 4212 T.D. 4350  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 095-21248 - 0000  
Spot Description: \_\_\_\_\_  
W/2 W/2 -SW Sec. 17 Twp. 30 S. R. 7 East  West   
1320 Feet from  North /  South Line of Section  
220 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Kingman *KCC*  
Lease Name: ~~EOG Johnson~~ EOG Well #: 1  
Date Well Completed: 9-3-82  
The plugging proposal was approved on: 12-21-10 (Date)  
by: Mr. Steve VanGeison (KCC District Agent's Name)  
Plugging Commenced: 12-21-10  
Plugging Completed: 12-23-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Mississippi	Oil Gas Water	Surface	8 5/8	247	-0-
		Production	4 1/2	4350	990

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

12-21-10 MIRU laydown rods 12-22-10 Lay down tubing. Set CIBP @4100' W/2sx. cement. Cut pipe @1303' & 990'. 12-23-10 Pull casing out of hole. Pump 50 sx. cement 750 to 600'. Pump 10 sx. cement from 300 to surface. Cut off & weld steel ID plate 4' BGL. RDMO Loc.

Plugging Contractor License #: 8733 Name: Jerry Dunkin, Inc.  
Address 1: P.O. Box 389 Address 2: \_\_\_\_\_  
City: Enid State: Okla Zip: 73702 + \_\_\_\_\_  
Phone: ( 580 ) 237-6152  
Name of Party Responsible for Plugging Fees: Linn Operating Inc. Attn: Rena Carter  
State of Oklahoma County, Oklahoma, ss.  
Rena Carter  Employee of Operator or  Operator on above-described well,

(Print Name)  
being first duly sworn on oath, says That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.  
Signature: Jerry Dunkin

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
JAN 04 2011  
KCC WICHITA