

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33999
Name: Linn Operating, Inc.
Address 1: 600 Travis/Suite 5100
Address 2: _____
City: Houston State: Tx Zip: 77002 + _____
Contact Person: Rena Carter
Phone: 405-241-2223
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Miss Sys Depth to Top: 4343 Bottom: 4355 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 095-21383 -0000
Spot Description: _____
SE NW SW-SW: Sec. 36 Twp 30 S. R. 7 East West
760 Feet from North / South Line of Section
560 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Kingman
Lease Name: Russell Well #: 2
Date Well Completed: 3-12-84
The plugging proposal was approved on: 12-8-10 (Date)
by: Mr Steve Van Geison (KCC District Agent's Name)
Plugging Commenced: 12-8-10
Plugging Completed: 12-13-10

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface, Conductor & Production) | | | |
|---------------------------|---------------|---|-------|---------------|------------|
| Formation | Content | Casing | Size | Setting Depth | Pulled Out |
| Miss Sys | Oil Water Gas | Surface | 8 5/8 | 355 | -0- |
| | | Production | 5 1/2 | 4773 | 1325 |
| | | | | | |
| | | | | | |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

12-8-10 MIRU. 12-9-10 POOHW rods & tubing. 12-10-10 Flush hole W/70 bbl mud set CIBP @4290' W/2 sx. cement on top cut casing @1325' POOHW casing. 12-13-10 Min & pump 50 sx. cement W/28 Cacl from 1300 to 1100'. Tag @918 Mix & pump 35 sx. cement W/2% Cacl from 750 to 650. Mix & pump 135 sx. cement W/2% Cacl From 400 to surface. Cut off welded steel ID plate . All plugs were circulated thru tubing.

Plugging Contractor License #: 8733 Name: Jerry Dunkin, Inc.
Address 1: P.O. Box 389 Address 2: _____
City: Enid State: Okla Zip: 73702 + _____
Phone: 580-237-6152
Name of Party Responsible for Plugging Fees: Linn Operating, Inc. Attn: Rena Carter
State of Okla County, Okla , ss.
Rena Carter Employee of Operator or Operator on above-described well.
(Print Name)

being first duly sworn or oath, says That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Jerry Dunkin

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
JAN 04 2011
KCC WICHITA