

**Notice:** Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117**

Form CP-4  
March 2009  
**Type or Print on this Form**  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 31327  
 Name: Pauley Oil  
 Address 1: 314 5th Street  
 Address 2: \_\_\_\_\_  
 City: Claffin State: KS Zip: 67525 + \_\_\_\_\_  
 Contact Person: Gary Pauley  
 Phone: ( 785 ) 252-8024  
 Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
 Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
 Producing Formation(s): List All (If needed attach another sheet)  
Arbuckle Depth to Top: 3283 Bottom: \_\_\_\_\_ T.D. 3286  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 053-00784:00 00  
 Spot Description: \_\_\_\_\_  
 NW NW SE NW Sec. 15 Twp. 17 S. R. 8  East  West  
3200 3820 Feet from  North /  South Line of Section  
3220 3820 Feet from  East /  West Line of Section  
 Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
 County: Ellsworth *KCC*  
 Lease Name: Kaka S Rolfs Well #: A 3  
 Date Well Completed: 8-3-51  
 The plugging proposal was approved on: 3-11-2011 (Date)  
 by: Virgil Clothier (KCC District Agent's Name)  
 Plugging Commenced: 3-14-2011  
 Plugging Completed: 3-15-2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8"	198	0
		Production	5 1/2	3283	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

On 3-10-11 an attempt was made to Produce the above well. We were able to drill down to 2880 and no futher due to junk in the hole. Called KCC for emergency plugging orders. Well Was plugged as follows. Perforated 1,150, 750, and 250. Triped in well with tubing and spotted 50 sx 60/40 on bottom. moved up hole and spotted 35 sx 60/40 at 1050. Moved up hole and spotted 35 sx at 750. Moved up hole and pumped 25 sx 60/40. Surface pipe was already full of cement witnessed by KCC. Topped well off with 10sx of 60/40

Plugging Contractor License #: 6901 Name: D. S. & W. Well Service  
 Address 1: 1822 24th Street Address 2: \_\_\_\_\_  
 City: Great Bend State: Kansas Zip: 67450 **APR 20 2011**  
 Phone: ( 620 ) 793-5838 **KCC WICHITA**  
 Name of Party Responsible for Plugging Fees: Pauley Oil  
 State of Kansas County, Ellsworth, ss. *ds*  
Gary Pauley  Employee of Operator or  Operator on above-described well,  
 (Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God

Signature: *Gary Pauley*