

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 31327
Name: Pauley Oil
Address 1: 314 5th Street
Address 2: _____
City: Cliffin State: KS Zip: 67525 + _____
Contact Person: Gary Pauley
Phone: (785) 252-8024
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3288 Bottom: _____ T.D. 3288
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 053-19125 00 00
Spot Description: _____
N2 NE SW NW Sec. 15 Twp. 17 S. R. 8 East West
3880 3923 KCC Feet from North / South Line of Section
4290 4380 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Ellsworth KCC
Lease Name: Kafka S. Rolfs Well #: 5
Date Well Completed: 10-5-51
The plugging proposal was approved on: 3-11-2011 (Date)
by: Virgil Clothier (KCC District Agent's Name)
Plugging Commenced: 3-16-2011
Plugging Completed: 3-22-2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	10"	199	0
		Production	7"	3288	0

RECEIVED
APR 20 2011
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

On 3-16-11 an attempt was made to Produce the above well. We were able to drill down to 2100 and no further due to junk in the hole. Called KCC for emergency plugging orders. Well Was plugged as follows. Perforated 2090, 1050, 750, and 250. Tripped in well with tubing and spotted 50 sx 60/40 on bottom. moved up hole and spotted 50 sx 60/40 and 2 sx cc. 100# hulls. Waited 2 hours. Tried to tag. No cement. Spotted another 50sx and 3 sx cc. Waited 2 hours. Tried to tag. No cement. 3-18-2011 pumped 200 sx 60/40, 25 sx Gel, 6 %cc, 400# hulls. 3-22-2011 Tag cement at 850. Moved up hole and spotted 50sx 60/40 4%gel at 750. Moved up hole to 250. Circulated to Surface with 100sx 60/40. Shut in backside and pumped 25 sx more. Hooked up Surface casing and pumped 75sx 60/40. Topped off with 25 sx 60/40. Next day, 3-23-11 Cement had dropped 2 feet from surface. Plugging complete.

Plugging Contractor License #: 6901 Name: D. S. & W. Well Service
Address 1: 1822 24th Street Address 2: _____
City: Great Bend State: Kansas Zip: 67450 + _____
Phone: (620) 793-5838

Name of Party Responsible for Plugging Fees: Pauley Oil
State of Kansas County, Ellsworth, ss.

Gary Pauley Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Gary Pauley

DP