

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 33999  
Name: Linn Operating Inc  
Address 1: 600 Travis Suite 5100  
Address 2: \_\_\_\_\_  
City: Houston State: TX Zip: 77002+  
Contact Person: Rena Carter  
Phone: ( 405 ) 241-2223  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Miss Depth to Top: 4190 Bottom: 4203 T.D. 4273  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 095-21378-00-00  
Spot Description: \_\_\_\_\_  
S/2 SW SE Sec. 18 Twp. 30 S. R. 7  East  West  
330 Feet from  North /  South Line of Section  
1980 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Kingman  
Lease Name: Earl Johnson A Well # 1  
Date Well Completed: 9-7-83  
The plugging proposal was approved on: 12-23-10 (Date)  
by: Mr Steve VanGeison (KCC District Agent's Name)  
Plugging Commenced: 12-23-10  
Plugging Completed: 12-29-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Miss	Oil Gas Water	Surface	8 5/8	249	-0-
		Production	4 1/2	4269	1293

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

12-23-10 MIRU unit,  
12-27-10 POOHW rods & tubing  
12-28-10 Set CIBP at 4100' w/2sx cement, cut & pull 4 1/2" casing at 1293', RIHW tubing to 1700', Pump 50sx cement 1300' to 1100', Tag at 1047', Pump 35sx cement 750' to 650', Pump 135sx cement 350' to surface,  
12-29-10 Cut off & weld steel ID plate 4' BGL

RECEIVED

JAN-07 2011

Plugging Contractor License #: 8733 Name: Jerry Dunkin INC  
Address 1: PO Box 389 Address 2: \_\_\_\_\_  
City: Enid State: Oklahoma Zip: 73702  
Phone: ( 580 ) 237-6152  
Name of Party Responsible for Plugging Fees: Linn Operating Inc Attn. Rena Carter  
State of Oklahoma County: Oklahoma, ss.  
Rena Carter  Employee of Operator or  Operator on above-described well,

KCC WICHITA

being first duly sworn on oath, says that I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.  
Signature: Jerry Dunkin