

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

Form CP-4 March 2009

Type or Print on this Form Form must be Signed All blanks must be Filled

WELL PLUGGING RECORD K.A.R. 82-3-117

OPERATOR: License #: 31691 Name: Coral Coast Petroleum, LC Address 1: 8100 E. 22nd St. North #600-R City: Wichita State: KS Zip: 67226 Contact Person: Daniel M. Reynolds Phone: (316) 269-1233 Type of Well: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (if needed attach another sheet) Viola Depth to Top: 6547 Bottom: 6550 T.D. 6600

API No. 15 - 025212780000 Spot Description: SW SW NW SE Sec. 10 Twp. 32 S. R. 22 East West 1,510 Feet from North South Line of Section 2,375 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Clark Lease Name: Thomas Well #: 1 Date Well Completed: 4-11-2005 The plugging proposal was approved on: 7-27-2010 (Date) by: Steve Durrant(witnessed by Jerry Stapleton) (KCC District Agent's Name) Plugging Commenced: 8-30-2010 Plugging Completed: 8-31-2010

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Row 1: Viola, 6547-50, Production, 5 1/2" 15.5#, 6598, 798 148 160.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

set standard bridge plug at 6500'. cut off casing at 798'. Cement with 2 sacks on top of bridge plug at 6500', 50 sacks at 1200', 50 sacks at 630', 20 sacks at 60', 60/40 poz with 4% gel.

RECEIVED FEB 02 2011

KCC WICHITA

Plugging Contractor License #: 4072 Name: H 2 Plains, LLC Address 1: P. O. Box 346 Address 2: City: Ness City State: Kansas Zip: 67560 Phone: (785) 798-3995

Name of Party Responsible for Plugging Fees: Coral Coast Petroleum, LC State of Kansas County, Sedgwick, ss.

Daniel M. Reynolds, Managing Member, Coral Coast Petroleum, LC Employee of Operator or Operator on above-described well, DR

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Daniel M. Reynolds, Managing Member, Coral Coast Petroleum, LC