

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 7116
Name: Kantor Oil Co LLC
Address 1: 15 W 6th
Address 2: Suite 2601
City: Tulsa State: OK Zip: 74119 + 5413
Contact Person: Larry Ressler
Phone: (620) 664-0597
Type of Well: (Check one) ☒ Oil Well ☐ Gas Well ☐ OG ☐ D&A ☐ Cathodic
☐ Water Supply Well ☐ Other: ☐ SWD Permit #: ☐
☐ ENHR Permit #: ☐ Gas Storage Permit #: ☐
Is ACO-1 filed? ☐ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No
Producing Formation(s): List All (If needed attach another sheet)
Miss Depth to Top: 3270 Bottom: 3430 T.D. 3415
Depth to Top: Bottom: T.D.
Depth to Top: Bottom: T.D.

API No. 15 - unknown **15-155-02791-00-00 KCC OK**
Spot Description:
C SW SE NW Sec. 12 Twp. 23 S. R. 4 ☐ East ☒ West
2,310 Feet from ☒ North / ☐ South Line of Section
1,650 Feet from ☐ East / ☒ West Line of Section
Footages Calculated from Nearest Outside Section Corner:
☐ NE ☒ NW ☐ SE ☐ SW
County: Reno
Lease Name: Neufeld Well #: 2
Date Well Completed: March 1937
The plugging proposal was approved on: 10-21-2010 (Date)
by: B J Hope (KCC District Agent's Name)
Plugging Commenced: 10-21-2010
Plugging Completed: 10-22-2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Miss	Oil Gas SW	yes prod.	7in.	3430	576 ft. 702' KCC
		surf.	12.5"	497'	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Day #1- Dump 140 gal. sand & bail 3 sx. cement to bottom. Tagged plug @ 50 ft. over perms. Pulled 576 ft. of casing. TIHW tubing. Pumped 100 sx. plug W/ 4% CC & 6 sx. hulls @ 690 ft. TOHW tubing. Wait 2 hrs. TIHW tubing. Tag plug @ 510 ft. Pulled 1 jt. Pumped 165 sx. plug W/ 4% CC @ 480 ft. TOHW tubing. Wait 1 hr. TIHW tubing. Tag plug @ 510 ft. Pull 1 jt. Pump 175 sx. plug, no CC W/ 300 lbs. hulls @ 480 ft. TOHW tubing. SDON. *Day #2- TIHW tubing. Tag Cement plug @ 105 ft. Perforated 13 3/8 surface @ 100 ft. W/ 8 holes. Welded cap on top of surface W/ 2 valve ports. Pumped surface pipe full of cement. Closed valve and pumped cement until good cement was circulating up on outside of surface pipe. Pumped a total of 140 sx. cement. Wait 1 hr. Cement did not fall. Job finished. KCC field rep. B J Hope was on location for entire job.

Plugging Contractor License #: 8253 Name: G & L Service
Address 1: 612 E Washington Address 2:
City: Sterling State: KS Zip: 67579 +
Phone: (620) 278-2703
Name of Party Responsible for Plugging Fees: Kantor Oil Co LLC
State of Oklahoma County, Tulsa, ss.
Larry Ressler ☒ Employee of Operator or ☐ Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Larry Ressler

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

FEB 01 2011

KCC WICHITA